



ESTIMATE

Tidewater Home Improvement LLC

Class B Contractor #2705172863

414 Worster Ave

Hampton, Virginia 23669

United States

(757) 551-6413

tidehomepro.com

BILL TO

Ernest Jack

Ernest Jack

3641 Old Forge Road

Virginia Beach, 23452

United States

774-200-3674

ejbrunelle5@yahoo.com

Estimate Number: 1372

Estimate Date: September 9, 2026

Valid Until: September 16, 2026

Grand Total (USD): **\$6,609.10**

Clean Up & Debris Removal

1172

Crawlspace clean up and debris removal, old vapor barrier and dead animal - 1,172 sq ft

10mil Vapor Barrier

1172

10-mil vapor barrier on full floor, taped seams and piers, up walls - 1,172 sq ft

Dehumidifier

1

AprilAire dehumidifier with condensation pump and discharge line

Electrical Outlet

1

Electrical - new circuit breaker and GFCI outlet with light, includes electrical permit

Seal Vents

1

Seal crawlspace vents with foam and wire mesh

Crawlspace Door

1

Crawlspace door made of PVC board

Military Discount

-734.34

Military Discount

Grand Total (USD):

\$6,609.10

Notes / Terms

Encapsulation of the crawlspace at 3641 Old Forge Road, Virginia Beach, VA. Moisture removal to address wavy and buckled hardwood floors in the hallway and dining room - no structural repairs required.

SCOPE OF WORK



ESTIMATE

Tidewater Home Improvement LLC

Class B Contractor #2705172863

414 Worster Ave

Hampton, Virginia 23669

United States

(757) 551-6413

tidehomepro.com

Crawlspace clean up and debris removal, old vapor barrier and dead animal removed: 1,172 sq ft.

10-mil vapor barrier on the full floor, taped seams and piers, up walls: 1,172 sq ft.

AprilAire dehumidifier with condensation pump and discharge line.

Electrical - new circuit breaker and GFCI outlet with light, includes electrical permit.

Crawlspace vents sealed with foam and wire mesh.

Crawlspace door replaced with a PVC board door.

Buried plumbing lines stay in place; above-ground lines are wrapped under the barrier and foam-sealed around.

NOT INCLUDED

Hardwood floor, tile, or subfloor replacement. Structural repairs. Mold treatment.

TERMS AND CONDITIONS

By agreeing to these Terms and Conditions, the customer acknowledges and accepts the outlined responsibilities and scope of work.

Notes:

**Jobsite will be left clean once completed.

**Contractor is not responsible for damage caused inside the home while repairing the foundation.

**Estimate valid until September 16, 2026.

**Military discount applied.

Warranty:

**12 months workmanship.

Payment Terms:

Total Project Cost: \$6,609.10

Deposit to Schedule: \$3,304.55

Final Payment: \$3,304.55

Check is a preferred method.

**You can pay by credit card using the link below.

<https://request.plastiq.com/pay-tidewater-home-improvement-llc>

Cards not eligible for payment:

- Virtual Affirm credit card